

**(ESPLOST) Woodville-Tompkins Gym Construction & Auditorium Renovation**

**Number: Bid C20-12**

**Posting Date: 10/13/19**

**Addenda # 3**

**Addenda Posting Date: 10-31-2019**

**Closing Date: 11/14/2019 11:00 am**

---

**The information contained in this document shall become an official part of the original document and shall be acknowledged as noted on the Certification Form of solicitation document in the space provided. Failure to acknowledge receipt of an addendum may result in a status of non-responsive. Firms are encouraged to review the contents of this document and to respond accordingly.**

**Addenda No. 3 is being issued to provide the following information and clarifications.**

**Question: Per the Sanitary Sewer Structure Table on C4.3, MH1 and MH4 are specified with being 6' in diameter. Gong by Savannah specs, I do not see a reason either should be in anything but a 4' diameter structure. Please confirm if this is correct or if I should quote them in 6' diameter.**

**Answer: The sanitary sewer system will be private, not owned and maintained by City of Savannah. Per JWB detail, manholes over existing pipes shall be 5' ID. Call-out changed in structure table.**

**Question: I do not see a detail for a "Chamber A/C/D MH" or a STMH in the provided details. They appear to be typical storm manholes that would be 4' diameter with a 195-E "Storm" casting. Please confirm if this is correct or specify what these structures require.**

**Answer: Still working with Storm Tech on specifics of the upstream manholes. However, these are usually 4' ID with weir plates on the inside. The downstream mh's are normal precast 4' ID.**

**Question: Drawing C5.0 detail 11 shows large double swing gates. The locations could not be found on the drawings. Please clarify where on the project these are located.**

**Answer: The gates are located on the new fencing adjacent to the existing childcare playground - See C2.2**

**Question: Drawings A6.7/A11.1 call out "Translucent Wall Panels". Please provide a spec section for these wall panels with manufacturer/product/model numbers. Also, please confirm that these go on both the left and right proscenium.**

**Answer: Section 06 6060 Translucent Panels will be issued in upcoming addendum. These installations are located on each side of the stage.**

**Question: Please provide a spec section for polished concrete.**

**Answer: We do not have polished concrete on this project.**

**\*\*\*ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED\*\*\***

**End of Addenda #3 to Bid C20-12**

**(ESPLOST) Woodville-Tompkins Gym Construction & Auditorium Renovation**